

Network Outcomes Contract Governance & Management Group Clarification

| | |
|-----------------------|--|
| Reference Number: | NOCC No. 17 |
| Subject Title: | OPM 50 Lined Surface Water Channels |
| Issue Date: | 26 September 2017 |
| Clarification Purpose | Clarification is provided to ensure the NOC is being interpreted consistently. The clarification does not remove or supersede the Network Outcomes Contract documentation. |

SUBJECT

This clarification is issued to explain the intent of the Contract Standard description for OPM 50. Contract extract:

| OPM GROUP 6.2.3: LINED SURFACE WATER CHANNELS (10% SAMPLE SIZE, MEASURED MONTHLY) | | | | |
|---|------------|--|---|---------|
| OPM | ROAD CLASS | CONTRACT STANDARD | DEFECT | PIP |
| 50 | All Roads | ≤ 3 defects per 100m of asset length, per audit section. | Isolated blockage that could allow water to pond or flow onto the carriageway or undermine the asset integrity. | 2 weeks |
| 51 | All Roads | No more than 5% of the asset length, in any audit section. | > 50% of the channel hydraulic cross-section inoperative. | 2 weeks |

RESPONSE

The intent of ‘≤ 3 defects per 100m of asset length, per audit section’ is that there are no more than 3 defects within any 100m length of lined surface water channel, not an average over the full audit section.